

Continuous Bead of SIP
Build Adhesive/Sealant

50mm Treated Softwood
End Blocking Glued and
Nailed in Place

Screws per Structural
Engineer's
Recommendations @
300mm c/c with
25mm Minimum
Penetration into
Support Below Spacings

Factory Cut
Chamfer to
Ridge Beam

Continuous Bead
of SIP Build
Adhesive/Sealant

2.8x63mm Galvanised
Ringshank Nails @
150mm c/c

Engineered Timber Beam
as Designed by the
Structural Engineer



Structural Insulated Panels

SIP Build Limited
Unit 2, Expressway Industrial Estate, Turnall Road, Ditton,
Widnes, Cheshire, WA8 8RB
Tel: 0870 850 2264 Fax: 0870 850 2265
Email: info@sipbuildltd.com

Drawing Title:

Ridge Details

Revisions:

Date:

October 2006

Drawn by:
KA

Scale:
1:5

SIP

R4