

LG Phillips Displays

Newport





Client:	LG Phillips Displays
Location:	Newport
Sector:	Manufacturing
TM services:	Machinery Movement
	Decommissioning of Services
	Waste Disposal Services

Scope of Project:

Decommissioning of colour tube production lines

Isolated and disconnected all mechanical pipe work and electrical services (415v and lower) prior to dismantling and removing Line W1 production equipment, utilising a fork lift truck fleet (up to 7 ton SWL) , 25 ton crane, 30ton versalift and appropriate lifting tackle, with a Mechanical & Electrical team of 20 personnel.

Production equipment included, TV screen manufacturing plant, 20 ton presses, conveyors, 30 metre furnaces, Lifts, 10km of conveyors & transfer equipment.

Trojan-Mek was also responsible for the safe disposal of more than 1,000 tons of scrap metal and other waste from the site, including some hazardous materials, which were chemically neutralised, then landfilled.

The project was completed successfully in conjunction with the Korean contractors Samil & Ooksan, and project managers, LPD Gumi.

"Trojan Mek accomplished every task they were assigned, in a timely and thoroughly professional manner... and I have no reservations in recommending them for any contract for which they are adjudged suitably qualified."

Nigel Fisher, Consultant Engineer